



**LOWER  
KUSKOKWIM  
SCHOOL  
DISTRICT**

**Capital Projects  
P.O. BOX 305 BETHEL, AK 99559  
Ph: 907-543-4903 FAX: 907-543-4908**

**Request for Proposal  
Emergency fuel oil storage tank facility  
Napakiak, AK**

**August 16, 2019**

LKSD is seeking cost proposals to deliver and place seven fuel oil storage tanks located in Bethel to the village of Napakiak. A secondary containment structure shall be constructed at the site prior to placement utilizing XR-5 geo-membrane liner and earthen berms. Once completed, proposer shall transfer all fuel out of the existing fuel storage facility to the new storage facility. Following completion of the fuel transfer, existing tanks shall be removed from the site and disposed of by legal means outside of the village.

The District has two tanks located at the old Kilbuck site that shall be relocated by the proposer to the Port of Bethel. The tanks are 3,000-gallon double wall skid mounted and 10,000-gallon cylindrical single wall. Three tanks will be available for pick up at the Port of Bethel and are 8,000-gallon double wall rectangular, 5,000-gallon single wall skid mounted, and 6,000-gallon double wall skid mounted. Two tanks are located at the City of Bethel Public Works Shop yard and are 2,000-gallon double wall skid mounted and 4,000-gallon double wall tank. The city tanks shall be delivered to the Port of Bethel by the proposer. Proposer shall be responsible to verify all tank dimensions as required for the successful performance of the work.

A 30mil XR-5 liner shall be used to construct the containment area in the school gravel parking lot. The area shall be 40'x84' clear inside the berms. Berms to be constructed of sandbags 3' high and 3' wide, with sandbag and gravel cap on exterior side of berm. Liner shall be a fully seamed, one-piece membrane, free of voids, tears and holes. See attached drawing details of liner and containment berm construction.

Contractor to be responsible to set tanks level and plumb inside the containment at locations shown in the attached detail drawings. Required cribbing and or dunnage is the responsibility of the proposer.

Work shall be completed by August 30, 2019. Cost proposals can be delivered to the LKSD business office, 1004 Ron Edwards Way, room 224, on or before 2pm, August 21, 2019.